

BRUHAT BANGALORE MAHANAGARA PALIKE


BBMP/2015-16/RD/WORK_INDENT18394/CALL-2

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/03/2015-16, Date: 22.01.2016

Construction of RCC Drain at Kamath Layout in ward no 10, (Doddabommasandra), Vidyaranyapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of		
				H V MADAN KUMAR		
				In Figures		In Words
1	180	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	83.0	14940.00	Rupees Eighty Three Only
2	22.5	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	4500.0	101250.00	Rupees Four Thousand Five Hundred Only
3	47.25	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 kgs, with 20mm and down size graded granite metal, coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum with superplastisiser @ 3lts confirming to IS 9103-1999 reaffirmed-2008 machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, walls (any thickness) including attached plasters, column, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour, HOM of machinery, curing, etc complete as per specifications and directions of engineer in charge of the work	Cum	5730.0	270742.50	Rupees Five Thousand Seven Hundred Thirty Only
4	2.84	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 TMT Bars FE 500 etc complete as per specifications and directions of engineer in charge of the work	Tonne	69000.0	195960.00	Rupees Sixty Nine Thousand Only
5	360	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work	Sqm	300.0	108000.00	Rupees Three Hundred Only
6	135	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar(1:6) including fixing curing etc, complete 7.5 cms thick etc complete as per specifications and directions of engineer in charge of the work	Sqm	600.0	81000.00	Rupees Six Hundred Only
7	750	KSRB 5-9: Providing chamfering edges to stone slab 2.5cms. wide as per specifications. (only chamfered length shall be recorded) etc complete as per specifications and directions of engineer in charge of the work	m	35.0	26250.00	Rupees Thirty Five Only


Executive Engineer
Byatarayanapura Division
Yalahanka Zone, B.B.M.P.
Bangalore-560092

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of		
				H V MADAN KUMAR		
				In Figures		In Words
8	135	KSRB 5-8.2 : Providing two line dressing to granite stone slab / granite stone masonry as per specifications.etc complete as per specifications and directions of engineer in charge of the work	Sqm	900.2 ✓	121527.00	Rupees Nine Hundred and Twenty Paise Only
9	180	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means including loading and unloading. From 0.00 to 11.90 Km etc complete as per specifications and directions of engineer in charge of the work	Cum	101.95 ✓	18351.00	Rupees One Hundred One and Ninety Five Paise Only
					938020.50	



Signature of the Contractor


 Executive Engineer
 Byarayanapura Division
 BBMP, Bangalore - 92

26/2/16